

Date: Jan. 10, 2022

Project: Canyon HS Football Retrofit
Santa Clarita, CA
Ref: 207558

Sourcewell

Master Project: 199030, Contract Number: 071619-MSL, Expiration: 08/27/2023

Category: Sports lighting with related supplies and services

All purchase orders should note the following:
Sourcewell purchase – contract number: 071619-MSL**Quotation Price – Materials Delivered to Job Site and Installation**

Football Stadium Lighting w/ Show-Light® – 360 'X 160'	\$448,566
Sales Tax (9.5%)	\$33,322.87
TOTAL	\$481,888.87

*Wholesaler/contractor markups, and DSA inspection fees are not included.**Pricing furnished is effective for 60 days unless otherwise noted and is considered confidential.**Divulging technical or pricing information to competitive vendors will result in removal from the bid list.***Light-Structure System™ retrofit with Total Light Control – TLC for LED™ technology****Guaranteed Lighting Performance**

- Guaranteed light levels of 70 fc and uniformity of 2:1
- BallTracker® technology – targeted light, optimizing visibility of the ball in play with no glare in the players typical line-of-sight

System Description [Light-Structure System™ retrofit]

- Factory wired poletop luminaire assemblies
- Factory aimed and assembled luminaires, including BallTracker® luminaires
- Factory wired and tested remote electrical component enclosures
- Pole length, factory assembled wire harnesses
- Mounting hardware for poletop luminaire assemblies and electrical components enclosures
- Disconnects
- UL Listed assemblies

Control Systems and Services

- Control-Link® control and monitoring system with Show-Light® entertainment package to provide pre-programmed theatrical shows, onsite dimming, and custom color accent lighting control.
- Touchscreen interface(s) to provide pre-programmed theatrical effects

Operation and Warranty Services

- Product assurance and warranty program that covers materials and onsite labor, eliminating 100% of your maintenance costs for 25 years
- Support from Musco's Lighting Services Team – over 170 Team members dedicated to operating and maintaining your lighting system – plus a network of 1800+ contractors



Installation Services Provided

[See attached scope of work]

Payment Terms

Musco's Credit Department will provide payment terms.

Email or fax a copy of the Purchase Order to Musco Sports Lighting, LLC:

Musco Sports Lighting, LLC
Attn: Amanda Hudnut
Fax: 800-374-6402
Email: musco.contracts@musco.com

All purchase orders should note the following:
Sourcewell purchase – contract number: 071619-MSL

Delivery Timing

8 - 12 weeks for delivery of materials to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole locations.

Due to the built-in custom light control per luminaire, pole locations need to be confirmed prior to production. Changes to pole locations after the product is sent to production could result in additional charges.

DSA Information Overview

DSA Inspection: The California Building Code, Title 24 requirements, states that a DSA approved inspector be present to inspect shop welding during production. Musco is providing this for informational purposes only and is not involved in the actual contracting of the inspectors or laboratories by the customer. Musco will, however, assist in coordinating the activities required to meet DSA requirements.

The DSA website can provide you with a list of approved labs. You may utilize any DSA-approved testing lab and Musco will assist in coordinating the individual inspections of welds. The inspection lab will work with Musco to schedule a time for inspection of welds on the poles at Musco Sports Lighting, LLC. Seam Weld Inspections (if required) is coordinated through Musco and Valmont at Valley Nebraska a Musco Vendor.

Delivery to the job site for DSA projects can vary from 6-14 weeks. Musco must have the following information in order to schedule production of a project:

1. Approved Submittals
2. Stamped/signed approved DSA drawings
3. Contact information for the DSA certified inspection lab and specific inspection requirements
4. Confirmation of order details including voltage/phase and pole locations. **(Due to the built-in custom light control per luminaire, pole locations need to be confirmed prior to production. Changes to pole locations after the product is sent to production could result in additional charges.)**



Notes

Quote is based on:

- Shipment of entire project together to one location.
- 480 Volt, 3 Phase electrical system requirement.
- Structural code and wind speed = 2019 CBC, 95 mi/h, Exposure C, Importance Factor 1.0.
- Owner is responsible for getting electrical power to the site, coordination with the utility, and any power company fees.
- Includes supply and installation of Musco system by a licensed contractor.
- Standard soil conditions – rock, bottomless, wet or unsuitable soil may require additional engineering, special installation methods and additional cost.
- Confirmation of pole locations prior to production.

Thank you for considering Musco for your lighting needs. Please contact me with any questions or if you need additional details.

Chris Hailey
Field Representative
Musco Sports Lighting, LLC
Phone: (818) 856-5068
E-mail: chris.hailey@musco.com

